

**Job ID:** JOB-0104  
**Project:** Sample Safety Building

### Summary by Subtotal

**Vendor:** TARGET

**Labor Level:** STANDARD

**1 Aug 2019 9:53:29**

#### Subtotal 2 - EMT

Item #	Size	Description	Q/M	Quantity	U/M	Mat Unit	Mat Result	Lab Unit	Lab Result	Quo Unit	Quo Result
10053	1/2	EMT	M	4,969.00	FT	0.3845	1,910.58	0.0256	127.43	0.0000	0.00
10054	3/4	EMT	M	21,379.00	FT	0.6779	14,492.82	0.0317	677.93	0.0000	0.00
10055	1	EMT	M	3,234.00	FT	1.1670	3,774.08	0.0247	79.92	0.0000	0.00
10056	1 1/4	EMT	M	1,543.00	FT	1.9129	2,951.60	0.0328	50.61	0.0000	0.00
10057	1 1/2	EMT	M	119.00	FT	2.3403	278.50	0.0360	4.28	0.0000	0.00
10058	2	EMT	M	80.00	FT	2.7307	218.46	0.0439	3.52	0.0000	0.00
10059	2 1/2	EMT	M	502.00	FT	4.1707	2,093.69	0.0518	25.98	0.0000	0.00
10060	3	EMT	M	139.00	FT	5.3525	744.00	0.0605	8.42	0.0000	0.00

**Subtotal totals: 26,463.73 978.08 0.00**

#### Subtotal 3 - PVC

Item #	Size	Description	Q/M	Quantity	U/M	Mat Unit	Mat Result	Lab Unit	Lab Result	Quo Unit	Quo Result
10165	1	PVC SCH 40	M	304.00	FT	0.3267	99.32	0.0235	7.15	0.0000	0.00
10176	1	PVC SCH 40 10' LAID IN TRENCH	M	1,430.00	FT	0.3267	467.18	0.0218	31.23	0.0000	0.00
10183	4	PVC SCH 40 10' LAID IN TRENCH	M	2,174.00	FT	1.8706	4,066.68	0.0286	62.23	0.0000	0.00

**Subtotal totals: 4,633.18 100.61 0.00**

#### Subtotal 8 - PVC FITTINGS

Item #	Size	Description	Q/M	Quantity	U/M	Mat Unit	Mat Result	Lab Unit	Lab Result	Quo Unit	Quo Result
20217	1	PVC SCH 40 90-DEG-ELBOW	M	44.00	EA	0.6457	28.41	0.1060	4.66	0.0000	0.00
31347	4	PVC FEMALE ADAPTER	M	112.00	EA	2.0546	230.12	0.2625	29.40	0.0000	0.00
31352	1	PVC MALE ADAPTER	M	20.00	EA	0.2569	5.14	0.1312	2.62	0.0000	0.00
31392	1	PVC COUPLING	M	76.00	EA	0.1644	12.49	0.0294	2.24	0.0000	0.00
40043	OUNCE	PVC (GLUE) CEMENT	M	443.80	OZ	0.3577	158.76	0.0078	3.48	0.0000	0.00
161375	1	PVC 2-HOLE STRAP	M	12.00	EA	0.5378	6.45	0.0331	0.40	0.0000	0.00

**Subtotal totals: 441.37 42.81 0.00**

#### Subtotal 10 - RIGID FITTINGS

Item #	Size	Description	Q/M	Quantity	U/M	Mat Unit	Mat Result	Lab Unit	Lab Result	Quo Unit	Quo Result
20076	4	GRC 90-ELBOW 36"R	M	56.00	EA	144.1700	8,073.52	2.6460	148.18	0.0000	0.00
40024	1/2	WP CONDUIT WALL SEAL	M	10.00	EA	0.0000	0.00	0.8269	8.27	0.0000	0.00
40128	3/4	GRND BUSHING INSULATED	M	2.00	EA	3.9286	7.86	0.2415	0.48	0.0000	0.00
40130	1 1/4	GRND BUSHING INSULATED	M	12.00	EA	5.0576	60.69	0.2677	3.21	0.0000	0.00
40131	1 1/2	GRND BUSHING INSULATED	M	2.00	EA	5.4892	10.98	0.2835	0.57	0.0000	0.00
40132	2	GRND BUSHING INSULATED	M	2.00	EA	7.1084	14.22	0.3150	0.63	0.0000	0.00
40232	1/2	PLASTIC BUSHING	M	26.00	EA	0.0659	1.71	0.0422	1.10	0.0000	0.00
40233	3/4	PLASTIC BUSHING	M	134.00	EA	0.0891	11.94	0.0363	4.86	0.0000	0.00
40234	1	PLASTIC BUSHING	M	230.00	EA	0.1469	33.79	0.0343	7.89	0.0000	0.00
40235	1 1/4	PLASTIC BUSHING	M	13.00	EA	0.1905	2.48	0.0525	0.68	0.0000	0.00
40236	1 1/2	PLASTIC BUSHING	M	2.00	EA	0.2490	0.50	0.0525	0.10	0.0000	0.00
40237	2	PLASTIC BUSHING	M	2.00	EA	0.4335	0.87	0.0525	0.10	0.0000	0.00
40238	2 1/2	PLASTIC BUSHING	M	12.00	EA	0.8592	10.31	0.0630	0.76	0.0000	0.00
40239	3	PLASTIC BUSHING	M	6.00	EA	0.9687	5.81	0.0630	0.38	0.0000	0.00

**Phone:**

**Web:**

**Subtotal 10 - RIGID FITTINGS**

Item #	Size	Description	Q/M	Quantity	U/M	Mat Unit	Mat Result	Lab Unit	Lab Result	Quo Unit	Quo Result
40245	3/4	EMT NM TERMINATOR	M	113.00	EA	0.0980	11.07	0.0352	3.98	0.0000	0.00
40246	1	EMT NM TERMINATOR	M	106.00	EA	0.3481	36.90	0.0315	3.34	0.0000	0.00
40255	1/2	LOCKNUT	M	4.00	EA	0.0976	0.39	0.0553	0.22	0.0000	0.00
40256	3/4	LOCKNUT	M	3.00	EA	0.1253	0.38	0.0588	0.18	0.0000	0.00
40257	1	LOCKNUT	M	16.00	EA	0.2192	3.51	0.0661	1.06	0.0000	0.00
40258	1 1/4	LOCKNUT	M	4.00	EA	0.3026	1.21	0.0735	0.29	0.0000	0.00
60000	1/2	GRC BUSHED CHASE NIPPLE	M	7.00	EA	0.5853	4.10	0.0740	0.52	0.0000	0.00
60001	3/4	GRC BUSHED CHASE NIPPLE	M	3.00	EA	0.8017	2.41	0.0756	0.23	0.0000	0.00
60003	1 1/4	GRC BUSHED CHASE NIPPLE	M	4.00	EA	2.1281	8.51	0.0840	0.34	0.0000	0.00

**Subtotal totals: 8,303.14 187.37 0.00**

**Subtotal 11 - EMT FITTINGS**

Item #	Size	Description	Q/M	Quantity	U/M	Mat Unit	Mat Result	Lab Unit	Lab Result	Quo Unit	Quo Result
20736	1/2	EMT FIELD-BEND	M	33.00	EA	0.0000	0.00	0.0827	2.73	0.0000	0.00
20737	3/4	EMT FIELD-BEND	M	331.00	EA	0.0000	0.00	0.1116	36.93	0.0000	0.00
20747	3/4	EMT 90-ELBOW	M	184.00	EA	1.9177	352.86	0.1772	32.61	0.0000	0.00
20749	1 1/4	EMT 90-ELBOW	M	32.00	EA	3.6849	117.92	0.2172	6.95	0.0000	0.00
20750	1 1/2	EMT 90-ELBOW	M	3.00	EA	4.2684	12.81	0.2768	0.83	0.0000	0.00
20751	2	EMT 90-ELBOW	M	3.00	EA	6.3009	18.90	0.3662	1.10	0.0000	0.00
20752	2 1/2	EMT 90-ELBOW	M	18.00	EA	14.1901	255.42	0.4394	7.91	0.0000	0.00
20753	3	EMT 90-ELBOW	M	9.00	EA	20.6358	185.72	0.5127	4.61	0.0000	0.00
30528	1/2	EMT STEEL-SS COUPLING	M	296.00	EA	0.3617	107.06	0.0157	4.66	0.0000	0.00
30529	3/4	EMT STEEL-SS COUPLING	M	1,859.00	EA	0.4368	812.01	0.0223	41.49	0.0000	0.00
30530	1	EMT STEEL-SS COUPLING	M	251.00	EA	0.5843	146.66	0.0188	4.71	0.0000	0.00
30531	1 1/4	EMT STEEL-SS COUPLING	M	178.00	EA	1.7506	311.61	0.0374	6.66	0.0000	0.00
30532	1 1/2	EMT STEEL-SS COUPLING	M	14.00	EA	1.6938	23.71	0.0517	0.72	0.0000	0.00
30533	2	EMT STEEL-SS COUPLING	M	10.00	EA	3.4062	34.06	0.0781	0.78	0.0000	0.00
30534	2 1/2	EMT STEEL-SS COUPLING	M	69.00	EA	8.2452	568.92	0.1172	8.09	0.0000	0.00
30535	3	EMT STEEL-SS COUPLING	M	25.00	EA	6.2056	155.14	0.1328	3.32	0.0000	0.00
30644	1/2	EMT STEEL SS CONNECTOR	M	646.00	EA	0.3125	201.87	0.0278	17.94	0.0000	0.00
30645	3/4	EMT STEEL SS CONNECTOR	M	2,115.00	EA	0.3039	642.75	0.0404	85.44	0.0000	0.00
30646	1	EMT STEEL SS CONNECTOR	M	218.00	EA	0.5112	111.44	0.0339	7.39	0.0000	0.00
30647	1 1/4	EMT STEEL SS CONNECTOR	M	38.00	EA	1.6594	63.06	0.0672	2.55	0.0000	0.00
30648	1 1/2	EMT STEEL SS CONNECTOR	M	2.00	EA	1.4363	2.87	0.0756	0.15	0.0000	0.00
30649	2	EMT STEEL SS CONNECTOR	M	2.00	EA	3.4319	6.86	0.1008	0.20	0.0000	0.00
30650	2 1/2	EMT STEEL SS CONNECTOR	M	12.00	EA	9.9366	119.24	0.1344	1.61	0.0000	0.00
30651	3	EMT STEEL SS CONNECTOR	M	6.00	EA	7.9049	47.43	0.1512	0.91	0.0000	0.00
161558	1/2	EMT 1-HOLE STEEL STRAP	M	46.00	EA	0.0802	3.69	0.0300	1.38	0.0000	0.00
161559	3/4	EMT 1-HOLE STEEL STRAP	M	424.00	EA	0.1180	50.03	0.0293	12.44	0.0000	0.00
161561	1 1/4	EMT 1-HOLE STEEL STRAP	M	12.00	EA	0.3143	3.77	0.0420	0.50	0.0000	0.00
161563	2	EMT 1-HOLE STEEL STRAP	M	2.00	EA	0.6577	1.32	0.0420	0.08	0.0000	0.00

**Subtotal totals: 4,357.14 294.70 0.00**

**Subtotal 13 - HANGERS/SUPPORTS**

Item #	Size	Description	Q/M	Quantity	U/M	Mat Unit	Mat Result	Lab Unit	Lab Result	Quo Unit	Quo Result
160001	3/4	CONDUIT HGR SNAP-CLS B-JOIST	M	218.00	EA	1.6629	362.51	0.0353	7.69	0.0000	0.00
160037	2 1/2	PLTD-MINI COND-HGR W/BOLT	M	76.00	EA	2.1523	163.57	0.1575	11.97	0.0000	0.00
160038	3	PLTD-MINI COND-HGR W/BOLT	M	23.00	EA	2.3621	54.33	0.1575	3.62	0.0000	0.00
160179	1/4-20	MALLEABLE BEAM CLAMP	M	20.00	EA	0.9064	18.13	0.1575	3.15	0.0000	0.00
160181	3/8-16	MALLEABLE BEAM CLAMP	M	99.00	EA	3.2371	320.47	0.1627	16.11	0.0000	0.00
160184	1/4-20	GALV BEAM CLAMP	M	98.00	EA	1.0002	98.02	0.1596	15.64	0.0000	0.00
160250	1/4 x 2 1/4"	PLTD WEDGE ANCHOR	M	24.00	EA	0.4951	11.88	0.1050	2.52	0.0000	0.00
160367	1/4 x 4"	TOGGLE BOLT	M	194.00	EA	0.3902	75.70	0.0554	10.75	0.0000	0.00
160390	#10	PLTD FLAT WASHER	M	617.00	EA	0.0190	11.72	0.0010	0.62	0.0000	0.00
160393	1/4"	PLTD FLAT WASHER	M	415.00	EA	0.0240	9.96	0.0011	0.44	0.0000	0.00
160395	3/8"	PLTD FLAT WASHER	M	196.00	EA	0.1200	23.52	0.0011	0.21	0.0000	0.00
160403	1/4"	PLTD LOCK WASHER	M	35.00	EA	0.0213	0.75	0.0011	0.04	0.0000	0.00
160405	3/8"	PLTD LOCK WASHER	M	196.00	EA	0.0344	6.74	0.0011	0.21	0.0000	0.00

Phone:

Web:

**Subtotal 13 - HANGERS/SUPPORTS**

Item #	Size	Description	Q/M	Quantity	U/M	Mat Unit	Mat Result	Lab Unit	Lab Result	Quo Unit	Quo Result
160472	1/4 x 1 1/4"	STN-STL FENDER WASHER	M	98.00	EA	0.2903	28.45	0.0011	0.10	0.0000	0.00
160779	1/4-20 x 1"	PLTD MACHINE SCREWS	M	1.00	EA	0.0527	0.05	0.0588	0.06	0.0000	0.00
160786	3/8-16 x 2"	PLTD MACHINE SCREWS	M	196.00	EA	0.1589	31.14	0.0630	12.35	0.0000	0.00
160928	1/4-20	PLTD HEX NUTS	M	377.00	EA	0.0321	12.10	0.0218	8.22	0.0000	0.00
160930	3/8-16	PLTD HEX NUTS	M	99.00	EA	0.0766	7.58	0.0315	3.12	0.0000	0.00
160941	1/4-20	GALV HEX NUTS	M	196.00	EA	0.1108	21.72	0.0210	4.12	0.0000	0.00
161114	#10 x 1"	WOOD SCREW	M	20.00	EA	0.0570	1.14	0.0220	0.44	0.0000	0.00
161120	#10 x 1"	TEK SCREW	M	5,072.00	EA	0.0503	255.12	0.0153	77.37	0.0000	0.00
161124	#10 x 1"	SHEET METAL SCREW	M	144.00	EA	0.0460	6.62	0.0182	2.62	0.0000	0.00
161125	#12 x 1"	SHEET METAL SCREW	M	123.00	EA	0.0647	7.96	0.0189	2.32	0.0000	0.00
161158	#10-12 x 1"	PLASTIC ANCHOR	M	71.00	EA	0.0735	5.22	0.0149	1.06	0.0000	0.00
161159	#8-12 x 1 1/4"	PLASTIC ANCHOR	M	35.00	EA	0.0408	1.43	0.0155	0.54	0.0000	0.00
161171	1/4 x 1 1/2 - 3"	HAMMER DRILLED HOLE	M	86.00	EA	0.0000	0.00	0.0978	8.41	0.0000	0.00
161173	3/8 x 1 1/2 - 3"	HAMMER DRILLED HOLE	M	44.00	EA	0.0000	0.00	0.1052	4.63	0.0000	0.00
161196	7"	TIE-WRAP	M	294.00	EA	0.1839	54.07	0.0220	6.48	0.0000	0.00
161238	1/4-20	GALV THREADED ROD	M	784.00	FT	0.8683	680.75	0.0525	41.16	0.0000	0.00
161350	24"	T-BAR BOX HANGER	M	8.00	EA	6.7120	53.70	0.0315	0.25	0.0000	0.00
240122	1 5/8" x 1 5/8"H	14G STRUT CHNL 1-1/8"SLOT GALV	M	147.00	FT	7.8739	1,157.46	0.0840	12.35	0.0000	0.00
240123	1 5/8" x 1 5/8"H	14G STRUT CHNL 1-1/8"SLOT PLAIN	M	50.00	FT	5.5724	278.62	0.0840	4.20	0.0000	0.00
240309	1/4-20	STRUT COMBO-NUT/SQ WASHER-ZN	M	98.00	EA	3.2496	318.46	0.0420	4.12	0.0000	0.00
630054	1/2 3/4 or AC/MC	EMT SCREW-ON SUPPORT (USE W/1-1/2D BOX)	M	540.00	EA	0.4962	267.95	0.0333	18.00	0.0000	0.00
630055	1/2 3/4 or AC/MC	EMT SCREW-ON SUPPORT (USE W/2-1/8D BOX)	M	174.00	EA	0.5269	91.68	0.0336	5.85	0.0000	0.00
630063	1/2	COND SNP-CLOSE HGR TO SCR-ON STUD-WALL	M	58.00	EA	1.2673	73.50	0.0255	1.48	0.0000	0.00
630064	3/4	COND SNP-CLOSE HGR TO SCR-ON STUD-WALL	M	400.00	EA	1.2619	504.76	0.0297	11.87	0.0000	0.00
630065	1	COND SNP-CLOSE HGR TO SCR-ON STUD-WALL	M	649.00	EA	1.3191	856.10	0.0290	18.81	0.0000	0.00
630075	3/4	COND HAMMER-ON HGR 1/4-FLNG SNP-CLOSE HD	M	294.00	EA	1.5308	450.06	0.0406	11.93	0.0000	0.00
630077	1 1/4	COND HAMMER-ON HGR 1/4-FLNG SNP-CLOSE HD	M	204.00	EA	2.2446	457.90	0.0403	8.22	0.0000	0.00
630078	1 1/2	COND HAMMER-ON HGR 1/4-FLNG SNP-CLOSE HD	M	16.00	EA	2.3584	37.73	0.0447	0.71	0.0000	0.00
630079	2	COND HAMMER-ON HGR 1/4-FLNG SNP-CLOSE HD	M	11.00	EA	2.5225	27.75	0.0525	0.58	0.0000	0.00
630081	3/4	COND HAMMER-ON HGR 1/2-FLNG SNP-CLOSE HD	M	218.00	EA	1.4200	309.56	0.0406	8.84	0.0000	0.00
630110	1/2	COND HAMMER-ON HGR 1/4-FLNGE PUSH-IN HD	M	630.00	EA	1.5484	975.49	0.0318	20.02	0.0000	0.00
630111	3/4	COND HAMMER-ON HGR 1/4-FLNGE PUSH-IN HD	M	1,661.00	EA	1.6043	2,664.74	0.0336	55.75	0.0000	0.00
630295	14-2>10-3 & 3/8	AC/FLEX HGR PUSH-IN MTL/WOOD/STUD	M	228.00	EA	0.5046	114.04	0.0344	7.77	0.0000	0.00
630310		METAL/WOOD STUD PROTECTION PLATE	M	109.00	EA	0.1389	15.14	0.0336	3.66	0.0000	0.00
630382	350	4-Sq HGR SCREW TO STUD-WALL	M	32.00	EA	0.7269	23.26	0.0220	0.71	0.0000	0.00
630405	TSGB16	STUD BRACKET ADJ 11 TO 18" OC	M	41.00	EA	2.7613	113.21	0.0331	1.36	0.0000	0.00
630412	1/8 > 1/4" FLANGE	COMB BOX & 1/2 > 3/4" SNP CLS COND HGR	M	21.00	EA	5.0778	106.63	0.0328	0.69	0.0000	0.00
630496	3/8 PLAIN/THREAD ROD	COMB BOX & 1/2 > 3/4" SNP-CLS COND HGR	M	190.00	EA	4.9154	933.93	0.0369	7.01	0.0000	0.00
630500	THREAD ROD MOUNT	COMB BOX & 1/2 > 3/4" SNP-CLS COND HGR	M	104.00	EA	4.1779	434.50	0.0216	2.25	0.0000	0.00
630539	1/4-20	WASHER NUT 1/4-20	M	312.00	EA	0.2762	86.17	0.0210	6.55	0.0000	0.00
630571	1/4" FLANGE	HAMMER-ON FLANGE CLIP - 1/4-20 x 3/8 STD	M	689.00	EA	1.0254	706.50	0.0322	22.16	0.0000	0.00
630586	1/4-20 x 3/8 STUD	BOT-MNT RETANR HAMMER-ON 1/2"BEAM STRP	M	50.00	EA	4.9851	249.26	0.0551	2.76	0.0000	0.00
630748	3/4" DIA	J-HOOK -HOLE MOUNTED	M	21.00	EA	1.5957	33.51	0.0441	0.93	0.0000	0.00
630750	2" DIA	J-HOOK -HOLE MOUNTED	M	20.00	EA	2.7670	55.34	0.0551	1.10	0.0000	0.00
<b>Subtotal totals:</b>						<b>13,667.61</b>		<b>485.88</b>		<b>0.00</b>	

**Subtotal 14 - FLEXIBLE CONDUIT**

Item #	Size	Description	Q/M	Quantity	U/M	Mat Unit	Mat Result	Lab Unit	Lab Result	Quo Unit	Quo Result
50000	3/8	FLEXIBLE STEEL CONDUIT	M	6.00	FT	0.3892	2.34	0.0257	0.15	0.0000	0.00
50001	1/2	FLEXIBLE STEEL CONDUIT	M	84.00	FT	0.4301	36.13	0.0303	2.55	0.0000	0.00
50002	3/4	FLEXIBLE STEEL CONDUIT	M	12.00	FT	0.6217	7.46	0.0367	0.44	0.0000	0.00
50004	1 1/4	FLEXIBLE STEEL CONDUIT	M	18.00	FT	1.3972	25.15	0.0735	1.32	0.0000	0.00
<b>Subtotal totals:</b>						<b>71.07</b>		<b>4.47</b>		<b>0.00</b>	

**Subtotal 15 - LIQUIDTITE**

Item #	Size	Description	Q/M	Quantity	U/M	Mat Unit	Mat Result	Lab Unit	Lab Result	Quo Unit	Quo Result
50080	1/2	LIQUIDTITE CONDUIT	M	54.00	FT	0.6688	36.12	0.0294	1.59	0.0000	0.00
50081	3/4	LIQUIDTITE CONDUIT	M	66.00	FT	0.8581	56.63	0.0367	2.43	0.0000	0.00

Phone:

Web:

**Subtotal 15 - LIQUIDTITE**

Item #	Size	Description	Q/M	Quantity	U/M	Mat Unit	Mat Result	Lab Unit	Lab Result	Quo Unit	Quo Result
50083	1 1/4	LIQUIDTITE CONDUIT	M	18.00	FT	1.7115	30.81	0.0735	1.32	0.0000	0.00
50084	1 1/2	LIQUIDTITE CONDUIT	M	6.00	FT	3.2670	19.60	0.1102	0.66	0.0000	0.00
50085	2	LIQUIDTITE CONDUIT	M	6.00	FT	3.7640	22.58	0.1470	0.88	0.0000	0.00
<b>Subtotal totals:</b>						<b>165.74</b>		<b>6.88</b>		<b>0.00</b>	

**Subtotal 17 - GROUNDING**

Item #	Size	Description	Q/M	Quantity	U/M	Mat Unit	Mat Result	Lab Unit	Lab Result	Quo Unit	Quo Result
850006	5/8 x 8	COPPER GROUND ROD	M	8.00	EA	14.6200	116.96	1.0500	8.40	0.0000	0.00
850010	3/4 x 10	COPPER GROUND ROD	M	2.00	EA	27.1300	54.26	1.0500	2.10	0.0000	0.00
850055	5/8	GROUND ROD CLAMP	M	8.00	EA	1.6100	12.88	0.1050	0.84	0.0000	0.00
850056	3/4	GROUND ROD CLAMP	M	2.00	EA	2.1400	4.28	0.1050	0.21	0.0000	0.00
850081	1/2 > 1	WATERPIPE GRND CLMP #4 >4/0 CU	M	2.00	EA	18.3700	36.74	0.2887	0.58	0.0000	0.00
850163	1/4"x2"x24" CU	GROUND BUS BAR 21 PAIR 7/16 HOLES	M	1.00	EA	82.2500	82.25	1.5750	1.57	0.0000	0.00
850470	#3/0	CADWELD COPPER WIRE TO #4 HORIZ REBAR	M	1.00	EA	9.5500	9.55	1.0710	1.07	0.0000	0.00
<b>Subtotal totals:</b>						<b>316.92</b>		<b>14.77</b>		<b>0.00</b>	

**Subtotal 18 - FIXTURES**

Item #	Size	Description	Q/M	Quantity	U/M	Mat Unit	Mat Result	Lab Unit	Lab Result	Quo Unit	Quo Result
120624		CEILING TILE CUT OUT	M	11.00	EA	0.0000	0.00	0.0882	0.97	0.0000	0.00
120862	2 x 2	LED T-BAR LAY-IN FIXTURE	M	90.00	EA	0.0000	0.00	0.3307	29.77	0.0000	0.00
120863	2 x 4	LED T-BAR LAY-IN FIXTURE	M	46.00	EA	0.0000	0.00	0.3969	18.26	0.0000	0.00
120868	2 x 4	LED RECESSED GYPSUM BD FIXTURE	M	55.00	EA	0.0000	0.00	0.7910	43.51	0.0000	0.00
120872		LED RECESSED RND FIXTURE-LABOR	M	43.00	EA	0.0000	0.00	0.9647	41.48	0.0000	0.00
120880	48" LONG	LED SURFACE FIXTURE W/LENS	M	25.00	EA	0.0000	0.00	0.6946	17.36	0.0000	0.00
120887		LED SURFACE WALL-MOUNT LABOR	M	12.00	EA	0.0000	0.00	0.5788	6.95	0.0000	0.00
120889		LED SURFACE CEILING-MOUNT LABOR	M	18.00	EA	0.0000	0.00	1.1576	20.84	0.0000	0.00
120892		LED PENDANT MOUNT FIXTURE-LABOR	M	130.00	EA	0.0000	0.00	0.3412	44.35	0.0000	0.00
120916		EXIT SURFACE MTD 1-FACE	M	29.00	EA	0.0000	0.00	0.7717	22.38	0.0000	0.00
130097	50W	LED WALLPACK	M	87.00	EA	0.0000	0.00	0.9647	83.93	0.0000	0.00
130145	5" x 16 FT	OUTDOOR LIGHTING POLE STL/ALUM	M	10.00	EA	0.0000	0.00	3.1500	31.50	0.0000	0.00
130169	85W LED	OUTDOOR POLE MOUNTED SHOE-BOX	M	12.00	EA	0.0000	0.00	2.2050	26.46	0.0000	0.00
130314	400W HID	BLDG FACADE UP-LITE W/SAFETY-CVR	M	8.00	EA	0.0000	0.00	2.9190	23.35	0.0000	0.00
<b>Subtotal totals:</b>						<b>0.00</b>		<b>411.10</b>		<b>0.00</b>	

**Subtotal 20 - SUPPORTS FIXTURE**

Item #	Size	Description	Q/M	Quantity	U/M	Mat Unit	Mat Result	Lab Unit	Lab Result	Quo Unit	Quo Result
121316	515A	LAY-IN T-BAR CLIP UPTURNED LIP	M	272.00	EA	0.3778	102.76	0.0331	9.00	0.0000	0.00
121320		DROP WIRE (COLORED)	M	1,360.00	FT	0.0256	34.78	0.0110	14.99	0.0000	0.00
121342		ADJ FIXTURE T-BAR HANGER SET	M	22.00	EA	5.7650	126.83	0.0661	1.46	0.0000	0.00
<b>Subtotal totals:</b>						<b>264.37</b>		<b>25.45</b>		<b>0.00</b>	

**Subtotal 21 - DEVICES**

Item #	Size	Description	Q/M	Quantity	U/M	Mat Unit	Mat Result	Lab Unit	Lab Result	Quo Unit	Quo Result
140013	20A	DX RECEP COMMERCIAL GRADE	M	172.00	EA	3.0700	528.04	0.1408	24.22	0.0000	0.00
140014	20A	DX RECEP COMMERCIAL GRADE TR	M	17.00	EA	5.8700	99.79	0.1890	3.21	0.0000	0.00
140028	20A	DUPLEX GFCI RECEP COMM GRADE	M	83.00	EA	15.7700	1,308.91	0.2089	17.34	0.0000	0.00
140042	20A 2P3W	SGL RECP 125V N5-20R COMM-GRADE	M	42.00	EA	2.5500	107.10	0.1586	6.66	0.0000	0.00
140101	30A 2P3W	FLUSH RECEP 250V N6-30R	M	1.00	EA	10.5961	10.60	0.2625	0.26	0.0000	0.00
140108	30A 3P4W	FLUSH RECEP 250V N14-30R	M	1.00	EA	10.9874	10.99	0.3150	0.31	0.0000	0.00
140118	50A 3P3W	FLUSH RECEP 125/250V N10-50R	M	2.00	EA	3.3252	6.65	0.3675	0.73	0.0000	0.00
140236	20A	DUPLEX USB CHARGER TR RECEPTACLE -WHITE	M	6.00	EA	30.2400	181.44	0.2310	1.39	0.0000	0.00
140432	15A	1P TOGGLE COMMERCIAL -GRADE	M	1.00	EA	2.1100	2.11	0.1890	0.19	0.0000	0.00
140446	20A	1P TOGGLE COMMERCIAL -GRADE	M	10.00	EA	2.4200	24.20	0.1890	1.89	0.0000	0.00
140452	20A	3W TOGGLE COMMERCIAL -GRADE	M	11.00	EA	4.9500	54.45	0.2100	2.31	0.0000	0.00
140455	20A	4W TOGGLE COMMERCIAL -GRADE	M	4.00	EA	15.7900	63.16	0.2310	0.92	0.0000	0.00
140457	20A	2P TOGGLE COMMERCIAL -GRADE	M	3.00	EA	9.0300	27.09	0.2310	0.69	0.0000	0.00

Phone:

Web:

**Subtotal 21 - DEVICES**

Item #	Size	Description	Q/M	Quantity	U/M	Mat Unit	Mat Result	Lab Unit	Lab Result	Quo Unit	Quo Result
140600	CI-355	PIR OCCUPANCY SENSOR CEILING MTD 1200SF	M	29.00	EA	82.2200	2,384.38	0.2975	8.63	0.0000	0.00
141513	20A 2P3W 120V	WP CORD REEL W/5-20R CONNECTOR	M	10.00	EA	707.4800	7,074.80	0.4504	4.50	0.0000	0.00
580038	NT-600-WH	1P SLIDE DIMMER 600W 120V-WHITE	M	4.00	EA	33.5600	134.24	0.2940	1.18	0.0000	0.00
580379	NFTV-WH	1P FLUOR SLIDE DIMMER 0-10V-WHITE	M	24.00	EA	68.0100	1,632.24	0.2670	6.41	0.0000	0.00
581430	MSCL-VP153M-WH	ML VAC PIR SENSOR DIMMER 120V -WHITE	M	6.00	EA	38.4400	230.64	0.2625	1.57	0.0000	0.00
581438	MS-A102-WH	1P OCC/VAC DUAL TECH SENSOR SW-WHITE	M	18.00	EA	69.9600	1,259.28	0.2625	4.72	0.0000	0.00
<b>Subtotal totals:</b>						<b>15,140.10</b>		<b>87.16</b>		<b>0.00</b>	

**Subtotal 22 - PLATES**

Item #	Size	Description	Q/M	Quantity	U/M	Mat Unit	Mat Result	Lab Unit	Lab Result	Quo Unit	Quo Result
140709	1-TOGGLE	1G NYLON PLATE	M	19.00	EA	0.3700	7.03	0.0525	1.00	0.0000	0.00
140717	1-DUPLEX	1G NYLON PLATE	M	172.00	EA	0.4000	68.80	0.0391	6.73	0.0000	0.00
140722	1-DECORA	1G NYLON PLATE	M	95.00	EA	0.4700	44.65	0.0625	5.94	0.0000	0.00
140745	30>50A 2.15" HOLE	2G NYLON SGL RECEIPT PLATE	M	4.00	EA	2.8000	11.20	0.0630	0.25	0.0000	0.00
141105	NON-METALLIC	1G WP UNIV PLATE -IN USE	M	12.00	EA	6.4700	77.64	0.0840	1.01	0.0000	0.00
141127		1G WP SWITCH PLATE	M	3.00	EA	4.8881	14.66	0.0882	0.26	0.0000	0.00
141152		2G WP BLANK PLATE	M	9.00	EA	1.4920	13.43	0.0525	0.47	0.0000	0.00
<b>Subtotal totals:</b>						<b>237.41</b>		<b>15.66</b>		<b>0.00</b>	

**Subtotal 23 - STEEL BOXES**

Item #	Size	Description	Q/M	Quantity	U/M	Mat Unit	Mat Result	Lab Unit	Lab Result	Quo Unit	Quo Result
150006	1-1/2"D	4"SQ CMB-KO NO BRKT	M	361.00	EA	0.9324	336.60	0.1361	49.14	0.0000	0.00
150015	1-1/2"D	4"SQ CMB-KO CV- BRKT	M	431.00	EA	1.5467	666.63	0.1062	45.77	0.0000	0.00
150041	2-1/8"D	4"SQ CMB-KO NO BRKT	M	362.00	EA	1.2656	458.15	0.1192	43.15	0.0000	0.00
150043	2-1/8"D	4"SQ 1"-KO NO BRKT	M	106.00	EA	2.0512	217.43	0.0944	10.01	0.0000	0.00
150047	2-1/8"D	4"SQ CMB-KO CV- BRKT	M	85.00	EA	2.1589	183.51	0.1050	8.92	0.0000	0.00
150066	3/4"RISE 5.8-CI	1G 4"SQ PLASTER-RING	M	583.00	EA	0.6490	378.37	0.0432	25.20	0.0000	0.00
150072	FLAT	2G 4"SQ PLASTER-RING	M	14.00	EA	1.7290	24.21	0.0450	0.63	0.0000	0.00
150075	3/4"RISE 10.0-CI	2G 4"SQ PLASTER-RING	M	2.00	EA	1.2007	2.40	0.0525	0.10	0.0000	0.00
150083	3/4"RISE 5.0-CI	4"SQ BOX TO RND P-RING	M	28.00	EA	2.0112	56.31	0.0843	2.36	0.0000	0.00
150095		4"SQ BLANK CVR	M	666.00	EA	0.3582	238.56	0.0324	21.55	0.0000	0.00
150099	1/2"D 7.3-CI	4"SQ 1-SW RAISED CVR	M	1.00	EA	1.2572	1.26	0.0525	0.05	0.0000	0.00
150114	1/2"D 7.3-CI	4"SQ 20A SGL RAISED CVR	M	42.00	EA	1.4211	59.69	0.0441	1.85	0.0000	0.00
150130	1-1/2 D 29.5-CI	4-11/16" BOX /NO BRACKET 1/2KO	M	1.00	EA	8.6865	8.69	0.1260	0.13	0.0000	0.00
150134	2-1/8"D 42.0-CI	4-11/16" BOX /NO BRKT 1/2>3/4KO	M	1.00	EA	2.0067	2.01	0.1260	0.13	0.0000	0.00
150137	2-1/8"D 42.0-CI	4-11/16" BOX /NO BRKT 1-1/4KO	M	5.00	EA	5.0912	25.46	0.1285	0.64	0.0000	0.00
150139	2-1/8"D 42.0-CI	4-11/16" BOX FLT BRKT 3/4> 1" KO	M	2.00	EA	6.7667	13.53	0.1260	0.25	0.0000	0.00
150154	3/4"RISE 10.0-CI	2G 4-11/16" PLASTER-RING	M	2.00	EA	5.0050	10.01	0.0525	0.10	0.0000	0.00
150167		4-11/16" BLANK CVR	M	7.00	EA	0.7088	4.96	0.0319	0.22	0.0000	0.00
150198	1-1/2"D 15.8-CI	4" OCTAGON COMB KO	M	189.00	EA	1.2702	240.07	0.0862	16.29	0.0000	0.00
150210	1-1/2"D 15.5-CI	4" OCTAGON BX CLAMPS	M	8.00	EA	5.4592	43.67	0.0840	0.67	0.0000	0.00
150336	2-1/2"DEEP 15.0-CI	1G MASONRY-BOX	M	77.00	EA	5.5089	424.19	0.2205	16.98	0.0000	0.00
<b>Subtotal totals:</b>						<b>3,395.68</b>		<b>244.16</b>		<b>0.00</b>	

**Subtotal 24 - CAST BOXES**

Item #	Size	Description	Q/M	Quantity	U/M	Mat Unit	Mat Result	Lab Unit	Lab Result	Quo Unit	Quo Result
150494	2" DEEP 16.5-CI	1G ALUM WP BOX W/ 3 x 1/2"HUBS	M	3.00	EA	2.8026	8.41	0.2100	0.63	0.0000	0.00
150514	2" DEEP 29.0-CI	2G ALUM WP BOX W/ 4 x 3/4"HUBS	M	9.00	EA	9.2800	83.52	0.3150	2.83	0.0000	0.00
<b>Subtotal totals:</b>						<b>91.93</b>		<b>3.46</b>		<b>0.00</b>	

**Subtotal 26 - FLOOR BOXES**

Item #	Size	Description	Q/M	Quantity	U/M	Mat Unit	Mat Result	Lab Unit	Lab Result	Quo Unit	Quo Result
151519	3G	STEEL RECTANGLE WOOD FLOOR BOX	M	7.00	EA	0.0000	0.00	0.7350	5.14	0.0000	0.00
151549	DUPLEX FLAP	1G RECT SINGLE SERVICE COVER-BRASS	M	14.00	EA	0.0000	0.00	0.0525	0.73	0.0000	0.00
151551	GFCI/DECOR	1G RECT SINGLE SERVICE COVER-BRASS	M	7.00	EA	0.0000	0.00	0.0525	0.37	0.0000	0.00
151579	3G	RECTANGLE WOOD FLOOR CARPET FLANGE-BRASS	M	7.00	EA	0.0000	0.00	0.2625	1.84	0.0000	0.00

Phone:

Web:



**Subtotal totals: 0.00 8.08 0.00**

**Subtotal 27 - PULL BOXES**

Item #	Size	Description	Q/M	Quantity	U/M	Mat Unit	Mat Result	Lab Unit	Lab Result	Quo Unit	Quo Result
500180	1 1/4	ENCLOSURE HOLE PUNCH -STEEL	M	2.00	EA	0.0000	0.00	0.2205	0.44	0.0000	0.00
710127	6x6x4	PULL BOX-PAINT SCREW CVR W/KO	M	4.00	EA	9.2600	37.04	0.6300	2.52	0.0000	0.00
710222	12x12x6	PULL BOX-PAINT SCREW CVR NO/KO	M	1.00	EA	24.8100	24.81	1.3120	1.31	0.0000	0.00
710329	12x12x6	PULL BOX -HINGED CVR	M	14.00	EA	33.2500	465.50	1.2495	17.49	0.0000	0.00

**Subtotal totals: 527.35 21.77 0.00**

**Subtotal 29 - MISC WIRE/TECK CABLE**

Item #	Size	Description	Q/M	Quantity	U/M	Mat Unit	Mat Result	Lab Unit	Lab Result	Quo Unit	Quo Result
90251	#18 2/C Red	FIRE ALARM CABLE PLENUM UNSHIELDED(FPLP)	M	340.00	FT	0.1446	49.16	0.0088	3.00	0.0000	0.00
90253	#18 4/C Red	FIRE ALARM CABLE PLENUM UNSHIELDED(FPLP)	M	1,210.00	FT	0.2723	329.48	0.0107	12.98	0.0000	0.00
90267	#14 2/C Red	FIRE ALARM CABLE PLENUM UNSHIELDED(FPLP)	M	580.00	FT	0.2233	129.51	0.0147	8.53	0.0000	0.00
90269	#14 4/C Red	FIRE ALARM CABLE PLENUM UNSHIELDED(FPLP)	M	2,555.00	FT	0.4262	1,088.94	0.0176	45.07	0.0000	0.00
90333	#18 2/C Red	FA CABLE PLENUM UNSHLD ADDR (FPLP)	M	680.00	FT	0.3644	247.79	0.0088	6.00	0.0000	0.00
90378	23/4PR	CAT6A CABLE CMR NON-PLENUM -BLUE	M	4,080.00	FT	0.5962	2,432.33	0.0088	35.99	0.0000	0.00
90396	23/4PR	CAT6 CABLE CMR NON-PLENUM -BLUE	M	1,964.00	FT	0.3571	701.34	0.0110	21.65	0.0000	0.00
90405	24/4PR	CAT5e CABLE CM NON-PLENUM -BLUE	M	264.00	FT	0.1266	33.42	0.0105	2.77	0.0000	0.00
90407	24/4PR	CAT5e CABLE CMR NON-PLENUM -WHITE	M	655.00	FT	0.1062	69.56	0.0110	7.22	0.0000	0.00
90482	16/2PR	CNTRL CBL UNSHLD TWSTD PR	M	224.00	FT	0.4700	105.28	0.0125	2.80	0.0000	0.00
500127		PULL LINE (STRING)	M	6,962.00	FT	0.0216	150.41	0.0017	11.93	0.0000	0.00

**Subtotal totals: 5,337.25 157.93 0.00**

**Subtotal 31 - THHN/THWN CU**

Item #	Size	Description	Q/M	Quantity	U/M	Mat Unit	Mat Result	Lab Unit	Lab Result	Quo Unit	Quo Result
70032	14	THHN/THWN CU (STR)	M	228.00	FT	0.0740	16.72	0.0037	0.83	0.0000	0.00
70033	12	THHN/THWN CU (STR)	M	65,619.00	FT	0.1143	7,500.25	0.0030	198.41	0.0000	0.00
70034	10	THHN/THWN CU (STR)	M	5,526.00	FT	0.1787	987.50	0.0036	19.68	0.0000	0.00
70035	8	THHN/THWN CU (STR)	M	6,291.00	FT	0.2783	1,750.79	0.0052	32.76	0.0000	0.00
70036	6	THHN/THWN CU (STR)	M	501.00	FT	0.4157	208.27	0.0081	4.05	0.0000	0.00
70037	4	THHN/THWN CU (STR)	M	908.00	FT	0.6592	598.55	0.0070	6.38	0.0000	0.00
70038	3	THHN/THWN CU (STR)	M	1,342.00	FT	0.8250	1,107.15	0.0074	9.93	0.0000	0.00
70040	1	THHN/THWN CU (STR)	M	1,074.00	FT	1.3149	1,412.20	0.0140	15.00	0.0000	0.00
70041	1/0	THHN/THWN CU (STR)	M	426.00	FT	1.5866	675.89	0.0117	4.99	0.0000	0.00
70043	3/0	THHN/THWN CU (STR)	M	24.00	FT	2.4200	58.08	0.0191	0.46	0.0000	0.00
70051	600	THHN/THWN CU (STR)	M	928.00	FT	9.2109	8,547.72	0.0353	32.74	0.0000	0.00

**Subtotal totals: 22,863.12 325.21 0.00**

**Subtotal 33 - BARE & GREEN WIRE**

Item #	Size	Description	Q/M	Quantity	U/M	Mat Unit	Mat Result	Lab Unit	Lab Result	Quo Unit	Quo Result
70144	14	GREEN THHN CU (GRD 15A)	M	18.00	FT	0.0724	1.30	0.0037	0.07	0.0000	0.00
70145	12	GREEN THHN CU (GRD 20A)	M	21,675.00	FT	0.1168	2,531.64	0.0032	69.34	0.0000	0.00
70146	10	GREEN THHN CU (GRD 60A)	M	3,789.00	FT	0.1745	661.18	0.0043	16.19	0.0000	0.00
70147	8	GREEN THHN CU (GRD 100A)	M	2,220.00	FT	0.2788	618.94	0.0057	12.63	0.0000	0.00
70148	6	GREEN THHN CU (GRD 200A)	M	508.00	FT	0.4291	217.98	0.0078	3.99	0.0000	0.00
70219	8	BARE CU (SOL)	M	64.00	FT	0.2589	16.57	0.0071	0.46	0.0000	0.00
70231	3/0	BARE CU (STR)	M	52.00	FT	2.5265	131.38	0.0124	0.65	0.0000	0.00

**Subtotal totals: 4,178.99 103.32 0.00**

**Subtotal 35 - THHN/THWN ALUM**

Item #	Size	Description	Q/M	Quantity	U/M	Mat Unit	Mat Result	Lab Unit	Lab Result	Quo Unit	Quo Result
80004	1	THHN ALUM	M	402.00	FT	0.3445	138.49	0.0100	4.01	0.0000	0.00
80052	6	THHN COMPACT ALUM GRN (GRD 100A)	M	134.00	FT	0.1847	24.75	0.0058	0.77	0.0000	0.00

**Subtotal totals: 163.24 4.78 0.00**

**Subtotal 36 - XHHW ALUM**

Phone:

Web:

**Subtotal 36 - XHHW ALUM**

Item #	Size	Description	Q/M	Quantity	U/M	Mat Unit	Mat Result	Lab Unit	Lab Result	Quo Unit	Quo Result
80076	250	XHHW ALUM	M	276.00	FT	0.9395	259.30	0.0214	5.91	0.0000	0.00
80095	250	XHHW COMPACT ALUM	M	2,344.00	FT	0.8091	1,896.53	0.0214	50.21	0.0000	0.00
80096	300	XHHW COMPACT ALUM	M	724.00	FT	1.0818	783.22	0.0234	16.95	0.0000	0.00
80106	4.	GREEN XHHW COMPACT ALUM (GRD 200A)	M	92.00	FT	0.2023	18.61	0.0079	0.72	0.0000	0.00
80107	2.	GREEN XHHW COMPACT ALUM (GRD 300A)	M	181.00	FT	0.2683	48.56	0.0100	1.81	0.0000	0.00
80109	1/0	GREEN XHHW COMPACT ALUM (GRD 500A)	M	586.00	FT	0.4518	264.75	0.0156	9.17	0.0000	0.00
<b>Subtotal totals:</b>						<b>3,270.98</b>		<b>84.77</b>		<b>0.00</b>	

**Subtotal 37 - ROMEX/BX/UF/MC**

Item #	Size	Description	Q/M	Quantity	U/M	Mat Unit	Mat Result	Lab Unit	Lab Result	Quo Unit	Quo Result
70338	12/2	MC CABLE - ALUM JKT W/G	M	2,193.00	FT	0.4085	895.84	0.0187	40.95	0.0000	0.00
70339	12/3	MC CABLE - ALUM JKT W/G	M	214.00	FT	0.7763	166.13	0.0216	4.62	0.0000	0.00
90154	18/2	FIRE ALARM MC/FPLP CABLE -RED	M	680.00	FT	1.4443	982.12	0.0093	6.34	0.0000	0.00
<b>Subtotal totals:</b>						<b>2,044.09</b>		<b>51.91</b>		<b>0.00</b>	

**Subtotal 42 - WIRE TERMINATIONS**

Item #	Size	Description	Q/M	Quantity	U/M	Mat Unit	Mat Result	Lab Unit	Lab Result	Quo Unit	Quo Result
100093	8	ALUM / CU SPLIT BOLT	M	16.00	EA	2.7000	43.20	0.3675	5.88	0.0000	0.00
100094	6.	ALUM / CU SPLIT BOLT	M	6.00	EA	2.8900	17.34	0.4042	2.43	0.0000	0.00
100095	4.	ALUM / CU SPLIT BOLT	M	9.00	EA	3.3200	29.88	0.4410	3.97	0.0000	0.00
100097	2.	ALUM / CU SPLIT BOLT	M	21.00	EA	4.8900	102.69	0.6247	13.12	0.0000	0.00
100101	3/0	ALUM / CU SPLIT BOLT	M	3.00	EA	13.5800	40.74	1.1760	3.53	0.0000	0.00
100118	2-2/0	SPLIT BOLT INSULATING CVR	M	21.00	EA	3.5700	74.97	0.1050	2.20	0.0000	0.00
100119	2/0-250	SPLIT BOLT INSULATING CVR	M	3.00	EA	15.8977	47.69	0.1050	0.31	0.0000	0.00
100136	#18 to 10	WIRE-NUT SML -YELLOW	M	1,580.00	EA	0.0917	144.89	0.0359	56.68	0.0000	0.00
100138	#18 to 8	WIRE-NUT MED -RED	M	2,954.00	EA	0.0666	196.74	0.0433	127.76	0.0000	0.00
100148		GROUND SCREW	M	59.00	EA	0.0474	2.80	0.0326	1.92	0.0000	0.00
100152	#12 SOL	8" PIGTAIL W/GRD SCREW	M	1,181.00	EA	0.4647	548.81	0.0425	50.22	0.0000	0.00
100210	14 - 6	SCRULUG OFFSET TONGUE -CU	M	10.00	EA	1.3600	13.60	0.0656	0.66	0.0000	0.00
100218	14 - 6	MECHL LUG AL/CU 1-WIRE 1H	M	1.00	EA	0.6000	0.60	0.0787	0.08	0.0000	0.00
100222	250	MECHL LUG AL/CU 1-WIRE 1H	M	1.00	EA	2.7100	2.71	0.2494	0.25	0.0000	0.00
100572	600	WIRE TERMINATION LBR	M	16.00	EA	0.0000	0.00	0.5460	8.74	0.0000	0.00
100704	#10 HOLE	NON-INSUL RING CRIMP LUG 18-14	M	8.00	EA	0.3418	2.73	0.0262	0.21	0.0000	0.00
100711	#10 HOLE	NON-INSUL RING CRIMP LUG 12-10	M	10.00	EA	0.4806	4.81	0.0318	0.32	0.0000	0.00
100742	#10 HOLE	INSULATED RING CRIMP LUG 12-10	M	8.00	EA	0.9529	7.62	0.0315	0.25	0.0000	0.00
100792	3/4"	BLACK ELECTRICAL TAPE (PER FOOT)	M	84.00	FT	0.0644	5.41	0.0031	0.26	0.0000	0.00
500205	1/4"	DRILL HOLE IN STEEL (UP TO 1/4" THICK)	M	1.00	EA	0.0000	0.00	0.0735	0.07	0.0000	0.00
670027	3/8	BX /MC 2-SCR SNGL STR-CONN	M	2.00	EA	0.8564	1.71	0.0808	0.16	0.0000	0.00
670032	3/8	BX /MC 1-SCR SNGL STR-CONN	M	278.00	EA	0.5878	163.41	0.0808	22.48	0.0000	0.00
670070	3/8 (38AST)	AC/MC SNAP 2-IT INSUL	M	313.00	EA	0.8075	252.75	0.0551	17.25	0.0000	0.00
670086	3/8 (383810AST)	AC/MC DX SNAP 2-IT SCR-CLP INS	M	71.00	EA	2.0039	142.28	0.0551	3.91	0.0000	0.00
670750	3/8-1/2	ANTI-SHORT	M	16.00	EA	0.0005	0.01	0.0126	0.20	0.0000	0.00
670751	SIZE 0	ANTI-SHORT 14/2 14/3 12/2	M	278.00	EA	0.0454	12.63	0.0105	2.92	0.0000	0.00
670758	3/4	METAL STUD BUSHING	M	14.00	EA	0.1422	1.99	0.0840	1.18	0.0000	0.00
<b>Subtotal totals:</b>						<b>1,862.01</b>		<b>326.98</b>		<b>0.00</b>	

**Subtotal 43 - SWITCHGEAR-PANELS**

Item #	Size	Description	Q/M	Quantity	U/M	Mat Unit	Mat Result	Lab Unit	Lab Result	Quo Unit	Quo Result
170027	1600A	DISTRIBUTION SWITCHBOARD 3-SECTION	M	1.00	EA	0.0000	0.00	43.6590	43.66	0.0000	0.00
170370	225A MLO 3PH4W	PNLBD W/BOLT-ON BKRS	M	3.00	EA	0.0000	0.00	3.9900	11.97	0.0000	0.00
170371	400A MLO 3PH4W	PNLBD W/BOLT-ON BKRS	M	3.00	EA	0.0000	0.00	5.7750	17.32	0.0000	0.00
<b>Subtotal totals:</b>						<b>0.00</b>		<b>72.95</b>		<b>0.00</b>	

**Subtotal 48 - MOTORS CONTROLS**

Item #	Size	Description	Q/M	Quantity	U/M	Mat Unit	Mat Result	Lab Unit	Lab Result	Quo Unit	Quo Result
200285		OVERLOAD HEATER	M	6.00	EA	23.5100	141.06	0.0630	0.38	0.0000	0.00

Phone:

Web:

**Subtotal 48 - MOTORS CONTROLS**

Item #	Size	Description	Q/M	Quantity	U/M	Mat Unit	Mat Result	Lab Unit	Lab Result	Quo Unit	Quo Result
200324	SIZE 0	575V 3-POLE N-1 PUSH-BUTTON MANUAL STARTER	M	2.00	EA	264.8600	529.72	1.3650	2.73	0.0000	0.00
200372	RAISE-LOWER-STOP	N-1 3-PB (2NO-3NC)	M	5.00	EA	149.9000	749.50	0.7350	3.67	0.0000	0.00
200848	5 HP	200/208 3PH VAR FREQUENCY DRIVE (VFD)	M	2.00	EA	0.0000	0.00	4.7460	9.49	0.0000	0.00
200849	7.5HP	200/208 3PH VAR FREQUENCY DRIVE (VFD)	M	2.00	EA	0.0000	0.00	4.9140	9.83	0.0000	0.00
200852	15 HP	200/208 3PH VAR FREQUENCY DRIVE (VFD)	M	2.00	EA	0.0000	0.00	5.4600	10.92	0.0000	0.00
<b>Subtotal totals:</b>						<b>1,420.28</b>		<b>37.02</b>		<b>0.00</b>	

**Subtotal 49 - EQUIPMENT TERMS**

Item #	Size	Description	Q/M	Quantity	U/M	Mat Unit	Mat Result	Lab Unit	Lab Result	Quo Unit	Quo Result
210025		ROOF-TOP EXHAUST FAN CONNECTION	M	3.00	EA	0.0000	0.00	1.5750	4.72	0.0000	0.00
210026		ROOF-TOP HVAC UNIT CONNECTION	M	4.00	EA	0.0000	0.00	2.6250	10.50	0.0000	0.00
210028		PAD MOUNT AC-UNIT CONNECTION	M	2.00	EA	0.0000	0.00	2.1000	4.20	0.0000	0.00
210035		UNIT HEATER CONNECTION	M	1.00	EA	0.0000	0.00	1.0500	1.05	0.0000	0.00
210042		AIR HANDLER UNIT CONNECTION	M	7.00	EA	0.0000	0.00	0.6345	4.44	0.0000	0.00
210136	3/4 HP	200/208V 3PH MOTOR CONNECTION	M	2.00	EA	0.0000	0.00	0.3675	0.73	0.0000	0.00
210141	5 HP	200/208V 3PH MOTOR CONNECTION	M	2.00	EA	0.0000	0.00	0.4725	0.94	0.0000	0.00
<b>Subtotal totals:</b>						<b>0.00</b>		<b>26.60</b>		<b>0.00</b>	

**Subtotal 50 - DISCONNECTS**

Item #	Size	Description	Q/M	Quantity	U/M	Mat Unit	Mat Result	Lab Unit	Lab Result	Quo Unit	Quo Result
220032	60/2 SN	F/HD/240V N-1 SAFETY-SW	M	1.00	EA	176.7800	176.78	1.4175	1.42	0.0000	0.00
220040	30/3 SN	F/HD/240V N-1 SAFETY-SW	M	1.00	EA	115.8800	115.88	1.2127	1.21	0.0000	0.00
220041	60/3 SN	F/HD/240V N-1 SAFETY-SW	M	2.00	EA	195.3900	390.78	1.7325	3.46	0.0000	0.00
220042	100/3 SN	F/HD/240V N-1 SAFETY-SW	M	3.00	EA	310.4600	931.38	2.3100	6.93	0.0000	0.00
220075	200/3 SN	F/HD/600V N-1 SAFETY-SW	M	1.00	EA	665.6100	665.61	4.0425	4.04	0.0000	0.00
220145	30/3 SN	F/HD/240V N-3R RT SAFETY-SW	M	2.00	EA	206.5500	413.10	1.1550	2.31	0.0000	0.00
220146	60/3 SN	F/HD/240V N-3R RT SAFETY-SW	M	2.00	EA	333.8800	667.76	1.7325	3.46	0.0000	0.00
220147	100/3 SN	F/HD/240V N-3R RT SAFETY-SW	M	2.00	EA	471.2700	942.54	2.3100	4.62	0.0000	0.00
220171	100/3	F/HD/600V N-3R RT SAFETY-SW	M	1.00	EA	586.3700	586.37	2.3100	2.31	0.0000	0.00
220195	200/3	NF/HD/600V N-3R RT SAFETY-SW	M	1.00	EA	543.3900	543.39	3.6750	3.67	0.0000	0.00
<b>Subtotal totals:</b>						<b>5,433.59</b>		<b>33.45</b>		<b>0.00</b>	

**Subtotal 51 - WIREMOLD**

Item #	Size	Description	Q/M	Quantity	U/M	Mat Unit	Mat Result	Lab Unit	Lab Result	Quo Unit	Quo Result
530048	WM G4000B	RACEWAY BASE GRAY	M	35.00	FT	0.0000	0.00	0.1176	4.12	0.0000	0.00
530049	WM G4000C	RACEWAY COVER GRAY	M	35.00	FT	0.0000	0.00	0.0294	1.03	0.0000	0.00
530535	WM G4000WC	RACEWAY WIRE CLIP	M	12.00	EA	0.0000	0.00	0.0367	0.44	0.0000	0.00
530547	WM G4010B	BLANK END FITTING -GRAY	M	3.00	EA	0.0000	0.00	0.0735	0.22	0.0000	0.00
530549	WM G4014A	WALL BOX CONNECTOR -GRAY	M	3.00	EA	0.0000	0.00	0.3675	1.10	0.0000	0.00
530632	WM G4047WX	1G DUPLEX RECEIPT COVER -GRAY	M	18.00	EA	0.0000	0.00	0.0735	1.32	0.0000	0.00
<b>Subtotal totals:</b>						<b>0.00</b>		<b>8.23</b>		<b>0.00</b>	

**Subtotal 53 - EMERGENCY GENERATOR**

Item #	Size	Description	Q/M	Quantity	U/M	Mat Unit	Mat Result	Lab Unit	Lab Result	Quo Unit	Quo Result
260025	400KW	GENERATOR	M	1.00	EA	0.0000	0.00	36.6030	36.60	0.0000	0.00
260038		GENERATOR REMOTE ANNUNCIATOR	M	1.00	EA	0.0000	0.00	1.5750	1.57	0.0000	0.00
260293	1600/4	AUTO-TRANSFER SW	M	1.00	EA	0.0000	0.00	32.0250	32.02	0.0000	0.00
<b>Subtotal totals:</b>						<b>0.00</b>		<b>70.20</b>		<b>0.00</b>	

**Subtotal 56 - CABLE TRAY**

Item #	Size	Description	Q/M	Quantity	U/M	Mat Unit	Mat Result	Lab Unit	Lab Result	Quo Unit	Quo Result
653619		CABLE TRAY BONDING JUMPER	M	38.00	EA	0.0000	0.00	0.1575	5.98	0.0000	0.00
653648	24" WIDTH	CABLE TRAY DROP OUT	M	2.00	EA	0.0000	0.00	0.4410	0.88	0.0000	0.00
653957	24"	ALUM LADDER CABLE TRAY 6"RUNGS-4"DEPTH	M	380.00	FT	0.0000	0.00	0.1191	45.25	0.0000	0.00
654037	24"	90D AL ELBOW-LADDER TRAY 6"RUNGS 4"DEPTH	M	2.00	EA	0.0000	0.00	2.6625	5.33	0.0000	0.00

Phone:

Web:



**Subtotal 56 - CABLE TRAY**

Item #	Size	Description	Q/M	Quantity	U/M	Mat Unit	Mat Result	Lab Unit	Lab Result	Quo Unit	Quo Result
654069	24"	TEE-HORIZ AL-LADDER TRAY 6"RUNGS 4"DEPTH	M	2.00	EA	0.0000	0.00	4.1840	8.37	0.0000	0.00
<b>Subtotal totals:</b>						<b>0.00</b>		<b>65.81</b>		<b>0.00</b>	<b>0.00</b>

**Subtotal 58 - SECURITY SYSTEMS**

Item #	Size	Description	Q/M	Quantity	U/M	Mat Unit	Mat Result	Lab Unit	Lab Result	Quo Unit	Quo Result
3000006		SURVEILLANCE PAN & TILT UNIT	M	48.00	EA	0.0000	0.00	1.0500	50.40	0.0000	0.00
3030050		SECURITY SYSTEM OVERHEAD DOOR CONTACT	M	14.00	EA	0.0000	0.00	0.5250	7.35	0.0000	0.00
3030083		ACCESS CONTROL CARD READER - WALL MTD	M	20.00	EA	0.0000	0.00	0.7350	14.70	0.0000	0.00
3030087		ACCESS CONTROL TOUCHPAD DOOR LOCK-NEW	M	18.00	EA	0.0000	0.00	1.5750	28.35	0.0000	0.00
3030101		ACCESS CONTROL REQUEST TO EXIT	M	17.00	EA	0.0000	0.00	0.7875	13.39	0.0000	0.00
3030102		ACCESS CONTROL DOOR CONTACT	M	24.00	EA	0.0000	0.00	0.7875	18.90	0.0000	0.00
<b>Subtotal totals:</b>						<b>0.00</b>		<b>133.09</b>		<b>0.00</b>	<b>0.00</b>

**Subtotal 60 - FIRE ALARM**

Item #	Size	Description	Q/M	Quantity	U/M	Mat Unit	Mat Result	Lab Unit	Lab Result	Quo Unit	Quo Result
320027		FIRE ALARM MONITOR MODULE	M	6.00	EA	0.0000	0.00	0.7350	4.41	0.0000	0.00
320046	16 ZONE	FIRE ALARM ANNUNCIATOR	M	1.00	EA	0.0000	0.00	5.1450	5.14	0.0000	0.00
320055		FIRE ALARM MANUAL STATION ADDRESSABLE	M	8.00	EA	0.0000	0.00	0.4200	3.36	0.0000	0.00
320058		FIRE ALARM SMOKE DETECTOR	M	8.00	EA	0.0000	0.00	0.5512	4.41	0.0000	0.00
320066		FIRE ALARM ADDRESSABLE BASE	M	14.00	EA	0.0000	0.00	0.5400	7.56	0.0000	0.00
320069		FIRE ALARM ADDRESSABLE HEAT DETECTOR	M	2.00	EA	0.0000	0.00	0.2100	0.42	0.0000	0.00
320070		FIRE ALARM ADDRESSABLE DUCT DETECTOR	M	12.00	EA	0.0000	0.00	1.9530	23.44	0.0000	0.00
320081		FIRE ALARM FLOW SWITCH	M	4.00	EA	0.0000	0.00	0.9450	3.78	0.0000	0.00
320082		FIRE ALARM TAMPER SWITCH	M	5.00	EA	0.0000	0.00	0.9450	4.72	0.0000	0.00
320088		FIRE ALARM STROBE LIGHT	M	3.00	EA	0.0000	0.00	0.5775	1.73	0.0000	0.00
320094		FIRE ALARM STROBE/SPEAKER	M	27.00	EA	0.0000	0.00	0.5775	15.59	0.0000	0.00
320129		FIRE ALARM REMOTE TEST SWITCH	M	8.00	EA	0.0000	0.00	0.5250	4.20	0.0000	0.00
<b>Subtotal totals:</b>						<b>0.00</b>		<b>78.77</b>		<b>0.00</b>	<b>0.00</b>

**Subtotal 64 - LOW VOLTAGE SYSTEMS**

Item #	Size	Description	Q/M	Quantity	U/M	Mat Unit	Mat Result	Lab Unit	Lab Result	Quo Unit	Quo Result
680101	661	BUZZACALL BUZZER 8-10VAC	M	1.00	EA	36.2200	36.22	0.5250	0.52	0.0000	0.00
680373	599	CLASS 2 SIGNAL TRANSFORMER-24V-40W-120V	M	1.00	EA	25.0100	25.01	0.2625	0.26	0.0000	0.00
680379	600	BRASS PUSHBUTTON 2-5/16 ROUND-SURF	M	2.00	EA	5.1500	10.30	0.1050	0.21	0.0000	0.00
680389	656-C	SATIN CHROME WP PUSHBUTTON W/PLATE	M	1.00	EA	56.2600	56.26	0.1050	0.10	0.0000	0.00
<b>Subtotal totals:</b>						<b>127.79</b>		<b>1.10</b>		<b>0.00</b>	<b>0.00</b>

**Subtotal 65 - TIME CLOCKS**

Item #	Size	Description	Q/M	Quantity	U/M	Mat Unit	Mat Result	Lab Unit	Lab Result	Quo Unit	Quo Result
510045	7200L	40A/120V/DPST RSV TIME-SW	M	1.00	EA	595.6700	595.67	1.0500	1.05	0.0000	0.00
<b>Subtotal totals:</b>						<b>595.67</b>		<b>1.05</b>		<b>0.00</b>	<b>0.00</b>

**Subtotal 66 - CONTACTORS**

Item #	Size	Description	Q/M	Quantity	U/M	Mat Unit	Mat Result	Lab Unit	Lab Result	Quo Unit	Quo Result
200567	30/8P	N-1 PWR/LIGHT CONTACT ELECT-HELD	M	1.00	EA	735.9500	735.95	2.2050	2.20	0.0000	0.00
<b>Subtotal totals:</b>						<b>735.95</b>		<b>2.20</b>		<b>0.00</b>	<b>0.00</b>

**Subtotal 67 - INTER/BASE SPACERS**

Item #	Size	Description	Q/M	Quantity	U/M	Mat Unit	Mat Result	Lab Unit	Lab Result	Quo Unit	Quo Result
390097	4 x 2	CARLON SNAP-LOC BASE SPACER	M	18.00	EA	1.0764	19.38	0.0420	0.76	0.0000	0.00
390098	4 x 3	CARLON SNAP-LOC BASE SPACER	M	200.00	EA	1.4383	287.66	0.0367	7.35	0.0000	0.00
390117	4 x 2	CARLON SNAP-LOC INTERMEDIATE SPACER	M	18.00	EA	1.0344	18.62	0.0420	0.76	0.0000	0.00
390118	4 x 3	CARLON SNAP-LOC INTERMEDIATE SPACER	M	200.00	EA	1.2763	255.26	0.0367	7.35	0.0000	0.00
<b>Subtotal totals:</b>						<b>580.91</b>		<b>16.21</b>		<b>0.00</b>	<b>0.00</b>

Phone:

Web:

**Subtotal 71 - DEMOLITION**

Item #	Size	Description	Q/M	Quantity	U/M	Mat Unit	Mat Result	Lab Unit	Lab Result	Quo Unit	Quo Result
380001		DEMOLITION BY MAN HOUR	M	80.00	EA	0.0000	0.00	1.0500	84.00	0.0000	0.00
380023	24"	REMOVE EXISTING JUNCTION-BOX	M	5.00	EA	0.0000	0.00	0.7875	3.94	0.0000	0.00
380044	600A	REMOVE EXISTING DISCONNECT	M	1.00	EA	0.0000	0.00	4.2000	4.20	0.0000	0.00
380047		REMOVE METER SOCKET	M	4.00	EA	0.0000	0.00	1.5750	6.30	0.0000	0.00
380051	333 TO 500 KVA	REMOVE EXISTING TRANSFORMER	M	1.00	EA	0.0000	0.00	10.2900	10.29	0.0000	0.00
380070	10	EXISTING WIRE TO PULL OUT	M	600.00	FT	0.0000	0.00	0.0036	2.14	0.0000	0.00
<b>Subtotal totals:</b>						<b>0.00</b>		<b>110.87</b>		<b>0.00</b>	

**Subtotal 73 - FUSES**

Item #	Size	Description	Q/M	Quantity	U/M	Mat Unit	Mat Result	Lab Unit	Lab Result	Quo Unit	Quo Result
230309	20 AMP	RK1 250V FUSE	M	6.00	EA	20.5800	123.48	0.0210	0.13	0.0000	0.00
230312	30 AMP	RK1 250V FUSE	M	3.00	EA	21.6800	65.04	0.0220	0.07	0.0000	0.00
230313	35 AMP	RK1 250V FUSE	M	6.00	EA	52.3600	314.16	0.0210	0.13	0.0000	0.00
230314	40 AMP	RK1 250V FUSE	M	2.00	EA	51.5500	103.10	0.0210	0.04	0.0000	0.00
230316	50 AMP	RK1 250V FUSE	M	3.00	EA	46.0500	138.15	0.0210	0.06	0.0000	0.00
230317	60 AMP	RK1 250V FUSE	M	3.00	EA	43.8200	131.46	0.0210	0.06	0.0000	0.00
230319	80 AMP	RK1 250V FUSE	M	6.00	EA	97.9700	587.82	0.0210	0.13	0.0000	0.00
230321	100 AMP	RK1 250V FUSE	M	9.00	EA	94.4900	850.41	0.0210	0.19	0.0000	0.00
230354	100 AMP	RK1 600V FUSE	M	3.00	EA	107.6800	323.04	0.0210	0.06	0.0000	0.00
<b>Subtotal totals:</b>						<b>2,636.66</b>		<b>0.86</b>		<b>0.00</b>	

**Subtotal 74 - TRENCHING**

Item #	Size	Description	Q/M	Quantity	U/M	Mat Unit	Mat Result	Lab Unit	Lab Result	Quo Unit	Quo Result
390012	24" Dia	SONOTUBE CONCRETE FORM 72"H	M	8.00	EA	212.0000	1,696.00	0.9450	7.56	0.0000	0.00
390022	5/8"	LIGHT POLE BASE ANCHOR BOLTS (SET OF 4)	M	8.00	EA	0.0000	0.00	0.7350	5.88	0.0000	0.00
390023	3/4"	LIGHT POLE BASE ANCHOR BOLTS (SET OF 4)	M	8.00	EA	0.0000	0.00	1.1025	8.82	0.0000	0.00
390037		HAND FINISH CONCRETE POLE BASE	M	8.00	EA	0.0000	0.00	0.1890	1.51	0.0000	0.00
390050	24" DIA	POUR CONCRETE IN 72" HIGH POLE BASE	M	8.00	EA	0.0000	0.00	0.8400	6.72	0.0000	0.00
390282	8" WIDE	HAND TRIM ROCKY TRENCH	M	44.00	FT	0.0000	0.00	0.0210	0.92	0.0000	0.00
390584	3"	RED TRENCH CAUTION TAPE	M	380.00	FT	0.0337	12.81	0.0031	1.20	0.0000	0.00
390701	#3	STEEL REBAR	M	1,243.00	FT	0.5300	658.79	0.0210	26.10	0.0000	0.00
390703	#5	STEEL REBAR	M	384.00	FT	0.5700	218.88	0.0315	12.10	0.0000	0.00
390710		STEEL TIE WIRE	M	588.00	FT	0.0570	33.52	0.0210	12.35	0.0000	0.00
390713	24" WIDE	3" SAND BEDDING	M	44.00	FT	0.0000	0.00	0.0882	3.88	0.0000	0.00
390714	36" WIDE	3" SAND BEDDING	M	333.00	FT	0.0000	0.00	0.1102	36.71	0.0000	0.00
390737	3500#	CONCRETE	M	5.60	YD	108.5000	607.60	0.0000	0.00	0.0000	0.00
<b>Subtotal totals:</b>						<b>3,227.60</b>		<b>123.75</b>		<b>0.00</b>	

**Subtotal 81 - CORING & HOLES**

Item #	Size	Description	Q/M	Quantity	U/M	Mat Unit	Mat Result	Lab Unit	Lab Result	Quo Unit	Quo Result
10539	1/2	CORED HOLE UP TO 8" D	M	10.00	EA	0.0000	0.00	0.2756	2.76	0.0000	0.00
<b>Subtotal totals:</b>						<b>0.00</b>		<b>2.76</b>		<b>0.00</b>	

**Subtotal 86 - LIGHTING CONTROL SYS**

Item #	Size	Description	Q/M	Quantity	U/M	Mat Unit	Mat Result	Lab Unit	Lab Result	Quo Unit	Quo Result
880026		LOW VOLTAGE SWITCH 3-BUTTON	M	6.00	EA	0.0000	0.00	0.1470	0.88	0.0000	0.00
<b>Subtotal totals:</b>						<b>0.00</b>		<b>0.88</b>		<b>0.00</b>	

**Subtotal 92 - ELECTRONIC CABLES**

Item #	Size	Description	Q/M	Quantity	U/M	Mat Unit	Mat Result	Lab Unit	Lab Result	Quo Unit	Quo Result
90579	20/2C	UNSHLD CABLE 80D 300V STR	M	476.00	FT	0.2467	117.41	0.0084	4.00	0.0000	0.00
90592	18/2PR	UNSHLD CABLE 80D 300V STR	M	6,681.00	FT	0.7521	5,024.91	0.0109	72.54	0.0000	0.00
<b>Subtotal totals:</b>						<b>5,142.32</b>		<b>76.54</b>		<b>0.00</b>	

**Subtotal 99 - MISCELLANEOUS ITEMS**

Phone:

Web:

**Subtotal 99 - MISCELLANEOUS ITEMS**

Item #	Size	Description	Q/M	Quantity	U/M	Mat Unit	Mat Result	Lab Unit	Lab Result	Quo Unit	Quo Result
2		AIR COMPRESSOR CONNECTION	M	2.00	EA	0.0000	0.00	1.2500	2.50	0.0000	0.00
3		SUMP PUMP CONNECTION	M	1.00	EA	0.0000	0.00	1.2500	1.25	0.0000	0.00
<b>Subtotal totals:</b>						<b>0.00</b>		<b>3.75</b>		<b>0.00</b>	

**Subtotal 108 - C.T. & METERING**

Item #	Size	Description	Q/M	Quantity	U/M	Mat Unit	Mat Result	Lab Unit	Lab Result	Quo Unit	Quo Result
171304	48 x36 x12	PT/CT CABINET	M	1.00	EA	0.0000	0.00	3.6750	3.67	0.0000	0.00
171309	PT/CT RATED	METER SOCKET	M	1.00	EA	0.0000	0.00	3.1500	3.15	0.0000	0.00
<b>Subtotal totals:</b>						<b>0.00</b>		<b>6.82</b>		<b>0.00</b>	

**Subtotal 109 - GEAR & PANEL ACCYS**

Item #	Size	Description	Q/M	Quantity	U/M	Mat Unit	Mat Result	Lab Unit	Lab Result	Quo Unit	Quo Result
171437		EPO EMERGENCY POWER-OFF PUSHBUTTON	M	1.00	EA	74.8000	74.80	0.7875	0.79	0.0000	0.00
<b>Subtotal totals:</b>						<b>74.80</b>		<b>0.79</b>		<b>0.00</b>	

**Subtotal 112 - FLEX COND FITTINGS**

Item #	Size	Description	Q/M	Quantity	U/M	Mat Unit	Mat Result	Lab Unit	Lab Result	Quo Unit	Quo Result
50029	3/8	FLEX COND ANGLE CONN	M	1.00	EA	1.8256	1.83	0.0882	0.09	0.0000	0.00
50030	1/2	FLEX COND ANGLE CONN	M	14.00	EA	2.4410	34.17	0.1092	1.53	0.0000	0.00
50031	3/4	FLEX COND ANGLE CONN	M	2.00	EA	3.7709	7.54	0.1235	0.25	0.0000	0.00
50033	1 1/4	FLEX COND ANGLE CONN	M	3.00	EA	10.5421	31.63	0.1764	0.53	0.0000	0.00
50040	3/8	FLEX COND STRAIGHT CONN	M	1.00	EA	0.5412	0.54	0.0735	0.07	0.0000	0.00
50041	1/2	FLEX COND STRAIGHT CONN	M	14.00	EA	0.6787	9.50	0.0910	1.27	0.0000	0.00
50042	3/4	FLEX COND STRAIGHT CONN	M	2.00	EA	1.2435	2.49	0.1029	0.21	0.0000	0.00
50044	1 1/4	FLEX COND STRAIGHT CONN	M	3.00	EA	6.0277	18.08	0.1470	0.44	0.0000	0.00
50091	1/2	LIQUIDTITE 90D ANGLE CONNECTOR	M	9.00	EA	3.5107	31.60	0.1323	1.19	0.0000	0.00
50092	3/4	LIQUIDTITE 90D ANGLE CONNECTOR	M	11.00	EA	5.4545	60.00	0.1588	1.75	0.0000	0.00
50094	1 1/4	LIQUIDTITE 90D ANGLE CONNECTOR	M	3.00	EA	16.6028	49.81	0.2646	0.79	0.0000	0.00
50095	1 1/2	LIQUIDTITE 90D ANGLE CONNECTOR	M	1.00	EA	20.1310	20.13	0.3175	0.32	0.0000	0.00
50096	2	LIQUIDTITE 90D ANGLE CONNECTOR	M	1.00	EA	29.9755	29.98	0.3704	0.37	0.0000	0.00
50102	1/2	LIQUIDTITE STRAIGHT CONNECTOR	M	9.00	EA	2.6960	24.26	0.1102	0.99	0.0000	0.00
50103	3/4	LIQUIDTITE STRAIGHT CONNECTOR	M	11.00	EA	3.8464	42.31	0.1323	1.46	0.0000	0.00
50105	1 1/4	LIQUIDTITE STRAIGHT CONNECTOR	M	3.00	EA	10.9445	32.83	0.2205	0.66	0.0000	0.00
50106	1 1/2	LIQUIDTITE STRAIGHT CONNECTOR	M	1.00	EA	15.5381	15.54	0.2646	0.26	0.0000	0.00
50107	2	LIQUIDTITE STRAIGHT CONNECTOR	M	1.00	EA	28.5740	28.57	0.3087	0.31	0.0000	0.00
<b>Subtotal totals:</b>						<b>440.81</b>		<b>12.49</b>		<b>0.00</b>	

**Subtotal 113 - WOOD/LUMBER**

Item #	Size	Description	Q/M	Quantity	U/M	Mat Unit	Mat Result	Lab Unit	Lab Result	Quo Unit	Quo Result
500165	4 x 8 x 3/4	PLYWOOD BACKBOARD	M	4.00	EA	70.0000	280.00	1.0500	4.20	0.0000	0.00
<b>Subtotal totals:</b>						<b>280.00</b>		<b>4.20</b>		<b>0.00</b>	

**Subtotal 128 - FACEPLATES/HOUSINGS**

Item #	Size	Description	Q/M	Quantity	U/M	Mat Unit	Mat Result	Lab Unit	Lab Result	Quo Unit	Quo Result
1580692	41644-W	4-PORT QUICKPORT DECORA MM INSERT-WHITE	M	7.00	EA	3.9200	27.44	0.1470	1.03	0.0000	0.00
<b>Subtotal totals:</b>						<b>27.44</b>		<b>1.03</b>		<b>0.00</b>	

**Subtotal 129 - OUTLETS/MODS-COPPER**

Item #	Size	Description	Q/M	Quantity	U/M	Mat Unit	Mat Result	Lab Unit	Lab Result	Quo Unit	Quo Result
1000266	WHITE	CAT5E 568A/B MODULE	M	7.00	EA	3.4800	24.36	0.1260	0.88	0.0000	0.00
1000306	BLUE	CAT6 568A/B MODULE	M	21.00	EA	3.4800	73.08	0.1260	2.65	0.0000	0.00
<b>Subtotal totals:</b>						<b>97.44</b>		<b>3.53</b>		<b>0.00</b>	

**Subtotal 140 - TEST & VERIFY**

Phone:

Web:

**Subtotal 140 - TEST & VERIFY**

Item #	Size	Description	Q/M	Quantity	U/M	Mat Unit	Mat Result	Lab Unit	Lab Result	Quo Unit	Quo Result
1050006		CABLE TEST- 4PR UTP- VOICE	M	7.00	EA	0.0000	0.00	0.1470	1.03	0.0000	0.00
1050009		CABLE TEST- 4PR UTP- CAT6	M	21.00	EA	0.0000	0.00	0.1470	3.09	0.0000	0.00
1050032		LABEL- WORKAREA- VOICE	M	7.00	EA	0.0000	0.00	0.0210	0.15	0.0000	0.00
1050033		LABEL- WORKAREA- DATA	M	21.00	EA	0.0000	0.00	0.0210	0.44	0.0000	0.00
1050038		LABEL- HORIZ. CABLE- VOICE	M	7.00	EA	0.0000	0.00	0.0210	0.15	0.0000	0.00
1050039		LABEL- HORIZ. CABLE- DATA	M	21.00	EA	0.0000	0.00	0.0210	0.44	0.0000	0.00
1050045		LABEL- PATCH BLOCK PORT	M	7.00	EA	0.0000	0.00	0.0210	0.15	0.0000	0.00
1050046		LABEL- PATCH PANEL PORT	M	21.00	EA	0.0000	0.00	0.0210	0.44	0.0000	0.00
1050052		LABEL- LV SWITCH	M	12.00	EA	0.0000	0.00	0.0210	0.25	0.0000	0.00

**Subtotal totals: 0.00 6.13 0.00**

**Subtotal 154 - PATCH PANEL-ACCESS**

Item #	Size	Description	Q/M	Quantity	U/M	Mat Unit	Mat Result	Lab Unit	Lab Result	Quo Unit	Quo Result
1050080		4PR CABLE DRESS @ IDF	M	28.00	EA	0.0000	0.00	0.0262	0.73	0.0000	0.00
1050091		4PR UTP- TERM@ IDF- VOICE	M	7.00	EA	0.0000	0.00	0.0735	0.51	0.0000	0.00
1050092		4PR UTP- TERM@ IDF- DATA	M	21.00	EA	0.0000	0.00	0.0735	1.54	0.0000	0.00

**Subtotal totals: 0.00 2.79 0.00**

**Subtotal 200 - DITCH WITCH**

Item #	Size	Description	Q/M	Quantity	U/M	Mat Unit	Mat Result	Lab Unit	Lab Result	Quo Unit	Quo Result
390777	4">6"W 30"D	DITCH WITCH RT12 CLAY TRENCH	E	1,430.00	FT	0.0000	0.00	0.0271	38.73	3.0000	4,290.00

**Subtotal totals: 0.00 38.73 4,290.00**

**Subtotal 201 - BACKHOE**

Item #	Size	Description	Q/M	Quantity	U/M	Mat Unit	Mat Result	Lab Unit	Lab Result	Quo Unit	Quo Result
390344	24"W x 36"D	BACKHOE TRENCHING SANDY	E	377.00	FT	0.0000	0.00	0.0273	10.29	18.0000	6,786.00
390400	24"W 36"D	BACKHOE BACKFILL SANDY TRENCH	E	377.00	FT	0.0000	0.00	0.0840	31.67	0.0000	0.00

**Subtotal totals: 0.00 41.96 6,786.00**

**Job totals: 138,617.69 4,971.89 11,076.00**

Phone:

Web: